

BILLS OF QUANTITY

NAME OF THE WORK:- Construction of BDO Quarter inside Tileibani block office premises

AMOUNT PUT TO TENDER :- 1172521.00

NO	ITEM OF WORK	QUANTITY	UNIT	RATE (In Rs)	AMOUNT (In Rs)
1	Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the EIC.	42.19	Cum	274.39	11577
2	Filling foundation and plinth with good coarse sand including watering & ramming as directed by the Engineer in charge.	93.68	Cum	1163.61	109007
3	Cement Concrete M10(1:3:6) with 4cm size hard granite metal including cost, conveyance, royalty, taxes, watering and curing etc. complete.	16.22	Cum	5864.51	95122
5	RCC work of M-20 grade with 20mm downgraded size hard granite chips including hoisting and laying				
.1	Column Base	8.32	Cum	6092.82	50692
.2	Column & Beam	5.25	Cum	14909.36	78274
.3	Plinth Beam	3.56	Cum	6554.96	23336
.4	Lintel	2.36	Cum	10586.72	24985
.5	Chhaja	0.66	Sqm	6454.23	4260
.6	Roof Slab	11.40	Cum	10980.86	125182
7	Supplying, fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification.(Ground Floor)	26.82	Qtl	8813.59	236358
3	Fly Ash brick work with 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in foundation and plinth per cum.(In foundation)	19.63	Cum	5760.64	113081
3	Fly Ash brick work with 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in foundation and plinth per cum.(In Superstructure-Ground Floor)	36.43	Cum	5793.97	211074
0	12 mm thick cement plaster in cement mortar (1:6) out side/face brick walls etc complete.(Ground Floor)	119.21	Sqm	208.65	24873
1	16 mm thick cement plaster in CM (1 : 6) over brick work inside surface of the wall including cost carriage royalty taxes and watering & curing etc. complete(Ground Floor)	235.28	Sqm	274.99	64700
Total: 40 (Forty Items)Only					1172521

Rs.1172521.00

Total No. of pages (Enclosed) other than DTCN _____ pages.

Notes:- Contractor should not write anything except quoting of Percentage, Excess/ Less /Equal to the total Estimated cost upto two decimal
CONDITIONS:- All Materials, Labour, Machineries and Equipments required to complete the work in all respect be arranged by the tenderer at his
N.B:- GST, Income Tax, Royalties, Labour Cess as applicable will be deducted from the bill of the Contractor. For all above works the minimum

My/Our quoted rate is _____ % Excess over/Less than/Equal to the above tendered amount of
 Rs. _____
 _____ only (both in figures and words).


 Block Development Officer
 Tileibani Block


 Assistant Executive Engineer
 Tileibani Block

Addl. Executive officer (Tech)
 Zilla parishad, Deogarh


 Junior Engineer
 Tileibani Block

