

BOQ of GPLF Office Building-cum Market Complex at Tileibani

Sl. No.	Items	Unit	Quantity	Rate	Amount
1	Earth work excavation in hard soil within initial lead and lift as per the direction of the Engineer-in-charge.	cum	69.33	275.61	19107.08
2	Filling in foundation and plinth with sand well watered and rammed,etc.	Cum	15.61	572.94	8945.00
3	Cement concrete (1:3:6) with 4cm size hard granite crusher broken metal,etc.	Cum	8.09	6329.57	51187.00
4	Flyash Brick masonry in cement mortar (1:6) in foundation and plinth.	Cum	16.15	5837.64	94301.00
5	Flyash Brick masonry in cement mortar (1:6) in Superstructure,etc.	Cum	42.92	5870.97	252001.00
6	Flyash Brick masonry in cement mortar (1:6) in Superstructure,etc.	Cum	2.58	5870.97	15157.00
7	R.C.C.M-200 using 20 mm and down graded hard granite crusher broken chips,etc.				
a	Column base	Cum	13.07	6527.34	85294.00
b	Plinth band	Cum	4.73	6990.25	33060.00
c	Column & Beam	Cum	18.06	15371.65	277583.00
d	Lintel	Cum	2.85	11030.57	31427.00
e	Chajja / Roof slab	Cum	16.28	11428.25	186041.00
8	Supplying,fitting & placing uncoated HYSD bar reinforcement including all cost & carriage including labour charges,etc.	Qntl	61.75	8822.55	544782.00
9	2.5cm thick grading concrete(1:2:2) on roof slab with 4.7mm size h.g chips,etc.	Sqm	123.74	372.85	46137.00
10	6 mm.thick cement plaster in C.M.(1:4) for ceiling plaster including deep chiping,etc.	Sqm	135.40	181.42	24565.00
11	16 mm thick cement plaster in C.M.(1:6) in internal surface of wall,etc.	Sqm	304.97	283.28	86391.00
12	12 mm thick cement plaster in C.M.(1:6) in external surface of wall,etc.	Sqm	367.53	215.99	79382.00
13	Supplying fitting &fixing of MS Door & Window including all cost of material & Laour charges,etc.	Kg	2020.13	71.24	143914.00
14	Supplying fitting &fixing of PVC Door including all Cost & labour as per direction of E.I.C. (L.S.)	Each	2	5500.00	11000.00
15	Supplying, fitting and fixing vetrifed tile in dados of size 600mm x 600mm of approved make conforming to IS :13755 laid on 12 mm thick cement mortar (1:3) and filling joints with white cement of approved quality including cost of all work all materials, taxes, labour, T&P , etc. complete as per direction of Engineer-in-charge.	Sqm	15.47	1053.48	16296.00

	Supplying and fixing vitrified tile in floors of size 300mm of approved make conforming to IS :13755 laid on 20 mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all work all materials,taxes,labour, T&P ,etc. complete as per direction of Engineer-in-charge.	Sqm	95.36	1053.48	100456.00
17	Supplying, fitting and fixing Vitrified industrial floor Tile of size 300mmx300mm of approved make conforming to IS :13755 laid on 20 mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all work all materials,taxes,labour, T&P ,etc. complete as per	Sqm	10.83	1053.48	11411.00
18	Fixing the glazed tile cliding on wall over 12 mm thick C.P. (1:3) jointed with neat cement Slurry including cost of all materials, labour T&P etc required for the work all completeas per direction of Engineer-in-charge.	Sqm	27.48	942.22	25892.00
19	Two coats of enamel painting over one coat of primer to doors and windows,etc.	Sqm	107.53	230.45	24781.00
20	Finishing walls with Oil 'bound cement primer one coat to plaster surfaces,etc.	Sqm	764.95	77.64	59391.00
21	Two coats of weather coat of approved quality to out side finishing area,etc.	Sqm	367.53	109.75	40336.00
22	Two coats of plastic emulsion paint of approved quality to in side finishing area,etc.	Sqm	397.42	109.75	43617.00
	Sub Total =			Rs	2312454.08
23	Add for Steps, skylight, transperancy board, photograph, provision for Fire safety work, easy access of Divyangs like ramp, etc. and unforeseen items, if any.			Rs	33000.00
	Total =			Rs	2345454.08
	Grand Total =			Rs	2345454
Rupees (Twentythree Lakhs forty five thousand four hundred fifty four) only.					


Total No. of pages (Enclosed) other than DTCN _____ pages.

Notes:-Contractor should not write anything except quoting of Percentage,Excess/ Less /Equal to the total
CONDITIONS:-All Materials,Labour,Machinaries and Equipments required to complete the work in all respect be
N.B:-GST,Income Tax,Royalities,Labour Cess as applicable will be deducted from the bill of the Contractor.For
all above works the minium grade of cement OPC,TMT High strength steel Fe-500.

My/Our quoted rate is _____ % Excess over/Less than/Equal to the above tendered amount of

Rs. _____


_____ only(both in figures and words).


Block Development Officer
Tilalban Block


Assistant Executive Engineer
Tilalban Block

Signature of Contractor

Junior Engineer
Tilalban Block


Superintending Engineer
Deogarh Irrigation Division
DEOGARH

Administrative copy

Collector-cum-C.E.O
Tilalban Block, Deogarh
10/11/25