

B.O.Q

## Construction of 50 MT Godown with office building at Laimura PACS

| Sl. No. | Items  | Unit | Quantity | Rate     | Amount    |
|---------|--|------|----------|----------|-----------|
| 1       | Earth work excavation in hard soil within initial lead and lift as per the direction of the Engineer-in-charge.  | cum  | 65.25    | 275.61   | 17983.55  |
| 2       | Filling in foundation and plinth with sand well watered and rammed,etc.  | Cum  | 107.47   | 507.19   | 54508.00  |
| 3       | Cement concrete (1:3:6) with 4cm size hard granite crusher broken metal,etc.   | Cum  | 22.75    | 6406.46  | 145747.00 |
| 4       | Flyash Brick masonry in cement mortar (1:6) in foundation and plinth.  | Cum  | 40.13    | 6174.87  | 247798.00 |
| 5       | Flyash Brick masonry in cement mortar (1:6) in Superstructure,etc.   | Cum  | 53.38    | 6208.20  | 331394.00 |
| 6       | R.C.C.M-20 using 20 mm and down graded hard granite crusher broken chips,etc.  |      |          |          |           |
| a       | Column base  | Cum  | 8.64     | 6606.60  | 57081.00  |
| b       | Plinth band  | Cum  | 5.71     | 7069.51  | 40367.00  |
| c       | Column & Beam  | Cum  | 13.08    | 15450.91 | 202098.00 |
| d       | Lintel   | Cum  | 5.12     | 11109.83 | 56882.00  |
| e       | Chajja / Roof slab   | Cum  | 8.43     | 11507.51 | 97008.00  |
| 7       | Supplying,fitting & placing uncoated HYSD bar reinforcement including all cost & carriage including labour charges,etc.  | Qntl | 38.12    | 8828.86  | 336556.00 |
| 8       | CC (1:2:4) With 12mm C.B Chips   | Cum  | 9.87     | 7538.16  | 74402.00  |
| 9       | 6 mm.thick cement plaster in C.M.(1:4) for ceiling plaster including deep chipping,etc.  | Sqm  | 0.00     | 181.59   | 0.00      |
| 10      | 16 mm thick cement plaster in C.M.(1:6) in internal surface of wall,etc.   | Sqm  | 259.11   | 283.54   | 73468.00  |
| 11      | 12 mm thick cement plaster in C.M.(1:6) in external surface of wall,etc.   | Sqm  | 442.92   | 216.23   | 95773.00  |
| 12      | Supplying fitting &fixing of MS Door & Window including all cost of material & Laour charges,etc.  | Kg   | 797.58   | 73.30    | 58463.00  |
| 13      | Supplying fitting &fixing of PVC Door including all Cost & labour as per direction of E.I.C. (L.S.)  | Each |          | 5500.00  | 0.00      |
| 14      | Supplying, fitting and fixing vetrified tile in dados of size 600mm x 600mm of approved make conforming to IS :13755 laid on 12 mm thick cement mortar (1:3) and filling joints with white cement of approved quality including cost of all work all materials, taxes, labour, T&P , etc. complete as per direction of Engineer-in-charge. | Sqm  | 6.98     | 1064.09  | 7427.00   |
| 15      | Supplying, fitting and fixing vetrified tile in floors of size 600mm x 600mm of approved make conforming to IS :13755 laid on 20 mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all work all materials,taxes,labour, T&P ,etc. complete as per direction of Engineer-in-charge.   | Sqm  | 39.56    | 1064.09  | 42095.00  |
| 16      | M.S Shutter made out of M.S angle and sheet  | Sqm  | 4.44     | 3600.90  | 15988.00  |
| 17      | Supplying fitting and fixing of M.S Tubular truss & purlin including all cost , carriage etc (market rate )  | Qntl | 15.00    | 12507.10 | 187607.00 |

|   |   |      |        |           |                   |
|---|---|------|--------|-----------|-------------------|
| 18  | Manufacturing , supplying(50mmx100mmx50mm)5mm C channel purlin, runner and fender to plinth band (angular )including fabrication and fixing in position as directed by engineer in charge   | Qntl | 10.00  | 7935.30   | 79353.00          |
| 19  | Cost , supplying and labour for fixing of anticorrosive zinc aluminium alloy painted coloured steel roofing profile sheet of 0.45 mm thick in roof of godown including fixing of ridge caps with fasteners of approved specifications | Sqm  | 71.80  | 1007.40   | 72331.00          |
| 20  | Supplying fitting and fixing of Holding down bolts (600mmx20mm )& base plate of 8 mm thickness including all cost , carriage etc (market rate )   | nos. | 12.00  | 97.80     | 1174.00           |
| 21  | Finishing walls with waterproofing cement paints  | sqm  | 201.51 | 63.03     | 12701.00          |
| 22  | Anti termite treatment in foundations , trenches , flooring with approved chemicals   | Sqm  | 95.40  | 112.70    | 10752.00          |
| 23  | Labour charges for fixing glass strips of depth 0.05m in joints in floor including cost of glass per 1 metre  | Sqm  | 6.00   | 696.40    | 4178.00           |
| 24  | Supplying fitting and fixing of Steel ventilator glazed composite with M.S grill outside iron frame with glass pairs including supplying and fixing of putty & wire clips, screw & nails & cost of materials (market rate )           | Sqm  | 3.60   | 3380.20   | 12169.00          |
| 25  | Two coats of enamel painting over one coat of primer to doors and windows,etc.  | Sqm  | 256.05 | 230.45    | 59007.00          |
| 26  | Finishing walls with Oil 'bound cement primer one coat to plaster surfaces,etc.   | Sqm  | 563.95 | 77.64     | 43785.00          |
| 27  | Two coats of plastic emulsion paint of approved quality to in side finishing area,etc.  | Sqm  | 563.95 | 109.75    | 61894.00          |
| 28  | Cost of pre cast ventilators and bathroom door  | nos. | 1.00   | 1200.00   | 1200.00           |
| <b>Total =</b>  |   |      |        | <b>Rs</b> | <b>2501189.55</b> |
| <b>Grand Total =</b>  |   |      |        | <b>Rs</b> | <b>2501190</b>    |
| <b>Rupees (Twnty five lakhs one thosand one hundred ninety rupees ) only.</b> |   |      |        |           |                   |

Total No. of pages (Enclosed) other than DTCN \_\_\_\_\_ pages.

Notes:-Contractor should not write anything except quoting of Percentage,Excess/ Less /Equal to the total  
**CONDITIONS:-All Materials,Labour,Machinaries and Equipments required to complete the work in all respect be**  
**N.B:-GST,Income Tax,Royalties,Labour Cess as applicable will be deducted from the bill of the Contractor.For all**

My/Our quoted rate is \_\_\_\_\_ % Excess over/Less than/Equal to the above tendered amount of  
 Rs. \_\_\_\_\_  
 \_\_\_\_\_ only(both in figures and words).

  
 Block Development Officer  
 Tileibani Block

  
 Assistant Executive Engineer  
 Tileibani Block

Signature of Contractor  
  
 Addl. Executive officer (Tech )  
 Zilla parishad , Deogarh

  
 Junior Engineer  
 Tileibani Block

  
 Collector  
 Zilla Parishad, Deogarh 6/2/25