

**NAME OF THE WORK:- Imp of Kailash Heritage Site at Kailash , GP - Tainsar**


**AMOUNT PUT TO TENDER :- 932722.00**

SL NO	ITEM OF WORK	QUANTITY	UNIT	RATE (In Rs)	AMOUNT (In Rs)
1	Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the EIC.	33.92	Cum	281.71	9556
2	Filling foundation and plinth with good coarse sand including watering & ramming as directed by the Engineer in charge.	31.01	Cum	574.41	17812
3	Cement Concrete M10(1:3:6) with 4cm size hard granite metal including cost, conveyance, royalty, taxes, watering and curing etc. complete.	19.26	Cum	6374.88	122780
6	RCC wok of M-20 grade with 20mm downgraded size hard granite chips including hoisting and laying				
6.1	Column Base	8.64	Cum	6544.14	56541
6.2	Column & Beam	6.11	Cum	15458.04	94449
6.3	Plinth Beam	4.58	Cum	7008.94	32101
6.6	Roof Slab	11.92	Cum	11477.04	136806
7	Supplying ,fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification.(Ground Floor)	30.50	Qtl	8835.84	269493
8	Fly Ash brick work with 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cm2 with dimensional tolerance ±2 percent in cement mortar (1:6) in foundation and plinth per cum.(In foundation)	10.54	Cum	5876.10	61934
9	Fly Ash brick work with 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cm2 with dimensional tolerance ±2 percent in cement mortar (1:6) in foundation and plinth per cum.(In Superstructure-Ground Floor)	5.49	Cum	5909.43	32443
14	Providing and fixing vitrified tiles in floors, treads of steps and landing on 20mm th bed of cement mortar (1:4) (1 cement:4 sand) joined with neat cement slurry mixed with pigment to match the shade of tiles including rubbing, polishing including cost of tiles, conveyance, taxes & labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge	83.72	Sqm	1180.17	98807
<b>Total: 40 (Forty Items)Only</b>					<b>932722</b>
					<b>Rs.932722.00</b>


Total No. of pages (Enclosed) other than DTCN \_\_\_\_\_ pages.

Notes:-Contractor should not write anything except quoting of Percentage, Excess/ Less /Equal to the total Estimated cost upto two decimal  
 CONDITIONS:-All Materials, Labour, Machineries and Equipments required to complete the work in all respect be arranged by the tenderer at his  
 N.B:-GST, Income Tax, Royalties, Labour Cess as applicable will be deducted from the bill of the Contractor. For all above works the minimum

My/Our quoted rate is \_\_\_\_\_ % Excess over/Less than/Equal to the above tendered amount of  
 Rs. \_\_\_\_\_ only (both in figures and words).

  
 Block Development Officer  
 Tileibani Block

  
 Assistant Executive Engineer  
 Tileibani Block

  
 Junior Engineer  
 Tileibani Block

  
 Addl. Executive Officer (tech)  
 Zilla Parishad, Deogarh