

# BILLS OF QUANTITY

Name of the project- Additional Block office building

Sl. No.	Items	Unit	Quantity	Rate	Amount
1	16 mm thick cement plaster in C.M.(1:6) in internal surface of wall,etc.	Sqm	245.79	286.07	70314.00
2	12 mm thick cement plaster in C.M.(1:6) in external surface of wall,etc.	Sqm	188.29	217.50	40953.00
3	Supplying fitting & fixing of GI Door & Window including all cost of material & Laour charges,etc.	Kg	400.32	135.00	54043.00
4	Supplying, fitting and fixing of 32mm thick flush door shutter with approved quality of 30mm thick BWR block board pasted with 1mm thick sunmica on both side of approved design and quality including cost of all door fittings and fixtures etc. complete	sqm	5.04	10668.61	53770.00
5	Supplying , fitting and fixing of two track UPVC sliding window of approved make with 6mm thick glass of approved quality complete with frame, shutters and all fitting and fixtures. (SOR-2022, Page235, item No-12)	sqm	7.20	4960.97	35719.00
6	Supplying, fitting and fixing vetrified tile in dados of size 600mm x 600mm of approved make conforming to IS :13755 laid on 12 mm thick cement mortar (1:3) and filling joints with white cement of approved quality including cost of all work all materials, taxes, labour, T&P , etc. complete as per direction of Engineer-in-charge.	Sqm	71.09	1180.17	83899.00
7	Supplying, fitting and fixing vetrified tile in floors of size 600mm x 600mm of approved make conforming to IS :13755 laid on 20 mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all work all materials,taxes,labour, T&P ,etc. complete as per direction of Engineer-in-charge.	Sqm	144.85	1180.17	170942.00
8	False ceilling made out of 12 mm thick PVC ,P.O.P. Gypsum board ceilling fixed with frame made out of G.I.Perimetre channel runners (Gyp steel make or equivalent branded company) etc. and hanged from R.C.C. Roof slab on 600mm x 600mm grid including cost, conveyance and taxes of all materials with cost of labour and T&P required for the work complete as per direction of the Engineer-in-charge.	Sqm	111.63	2188.20	244269.00
9	Two coats of enamel painting over one coat of primer to doors and windows,etc.	Sqm	19.80	231.72	4588.00
10	Finishing walls with Oil 'bound cement primer one coat to plaster surfaces,etc.	Sqm	578.93	78.91	45683.00
11	Finishing wall surface with Acrylic wall putty of approved make & finished smooth & even surface to receive painting including cost of scaffolding staging charges with cost of all materials, taxes, labour with T&P etc. complete in all floors.	Sqm	578.93	84.94	49174.00
12	Two coats of plastic emulsion paint of approved quality to in side finishing area,etc.	Sqm	578.93	111.14	64342.00
13	Cost of Aluminium door	nos	2.00	6000.00	12000.00
	<b>Sub Total =</b>			<b>Rs</b>	<b>929696.00</b>

Pages (Enclosed) other than DTCN \_\_\_\_\_ pages.

Contractor should not write anything except quoting of Percentage, Excess/ Less /Equal to the total Estimated cost  
CONDITIONS:-All Materials, Labour, Machinaries and Equipments required to complete the work in all respect be arranged  
B:-GST, Income Tax, Royalties, Labour Cess as applicable will be deducted from the bill of the Contractor. For all above works the minium grade of cement OPC, TMT High strength steel Fe-500.

My/Our quoted rate is \_\_\_\_\_ % Excess over/Less than/Equal to the above tendered amount of  
Rs. \_\_\_\_\_

\_\_\_\_\_ only(both in figures and words).

Signature of Contractor

  
Block Development Officer  
Tileibani Block

  
Assistant Executive Engineer  
Tileibani Block

  
Junior Engineer  
Tileibani Block